

8-12

103

4-041437

E-17,919

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,198-00-00

SW /4 SEC. 23, 05 S, 20 W
1650 feet from S section line
3960 feet from E section line

Operator license# 5447 Lease Brown "B" well # 5W

Operator: OXY USA, Inc. County Phillips

Address: 110 S. Main Well total depth 3700 feet
#800 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 203 feet
w/150 sx.

120.25

Aband. oil well __, Gas well __, Input well X, SWD __, D & A __

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 12 Month: August Year: 92

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 4 1/2" casing set @ 3699' w/535 sx. cement. Perf. @ 3350' -
3439'. Perf. @ 1695'. Dakota @ 745'.
Order 300 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:45A.M., Day: 12, Month: August, Year: 92

Actual plugging report: M.I.R.U. P.O.O.H. with 2 3/8" tubing and
2 3/8" x 4 1/2" pkr. R.I.H. with W.L. to perf. @ 1695' and 1045'.
Rigged up HOWCO and pumped 25 sx. 60/40 pozmix - 10% gel. with 1/4#
flocele followed w/225 sx. cement with 1/4# F.C. plus hulls mixed
in cement. Max. 1000# P.S.I. S.I. 700# P.S.I.
Hooked-up to 8 5/8" S.P. Pumped in 75 sx. 60/40 pozmix - 10% gel. with
1/4# flocele. Max. 300#. S.I. 100#.

Remarks: RECEIVED
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES x, CALC X, NO Dakota plug: YES, NO
Plugged through TUBING, CASING X. Elevation: GL JAN 6 1993
I did X did not [] observe the plugging. Dennis L. Hamel
DIVISION
WICHITA, KANSAS

INVOICED

DATE 1-11-93

INV. NO. 37178

8-12-92 JAN 22 1993

(agent)
Form CP-2/3