

6 041171

5-2

15-147-0062000-00

60
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 12-7-46
NW NE SW
SEC. 23 T 5 S, R 20 W 7/8 X

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Brown Well # 2

Operator: Oxy USA Inc.

County Phillips 117.91

Name & Address: Box 26100

Well Total Depth 3628 feet

Oklahoma City, Ok. 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Russell, Ks.

Company to plug at: Hour: 9:00 AM Day: 2 Month: May Year: 19 90

Plugging proposal received from J. D. Hinger

(company name) Oxy USA (phone) _____

were: 5 1/2" casing set at 3579 w/150 sks cement;

perfs at 3273 - 3575'. Perf anhy at 1630' ; perf base dakota at 930'.

Ordered 400 sks 65/35 poz 8% gel w/1/4# f.c. plus 7 sks hulls.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 2 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing w/300 sks cement w/1/4# f.c. plus

5 sks hulls mixed in cement. Max 1000# S.I. 600#. Pumped in 8 5/8" casing w/

100 sks cement w/1/4# f.c. and 2 sks hulls mixed in cement. Max 500#. S.I. 300#.

05-16-1990

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

Remarks: (old) observe this plugging.

DATE MAY 22 1990

INV. NO. 28202

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel