

To: **6 041249**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA Inc.

Name & Address Box 26100

Oklahoma City, OK. 73126-0100

1-8 15-147-00619-00-094
API NUMBER 15-

7-22-44

SW 23, SEC. 5, T 20 S, R W/Ex

2310 feet from S section line

4290 feet from E section line

Lease Name Brown B Well # 1

County Phillips 116.44

Well Total Depth 3583 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 160 w/185 sks

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number

Address Oberlin, Ks.

Company to plug at: Hour: 8:00 Day: 8 Month: Jan Year: 19 90

Plugging proposal received from Jin Nowell

(company name) Oxy USA (phone)

were: 5 1/2 casing set at 3541 w/150 sks cement: perfs at 3246 to 3455;

Perf anhy at 1670; perf base dakota at 930; Fish in hole at 2670.

Ordered 470 sks 65/35 poz 8% gel w/ 1 lb f.c. plus 200 lbs. hulls.

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1991
01-15-1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

xx

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30PM Day: 8 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Run in tubing to 2630: spt 260 sks 65/35 poz 8% gel w/100 lbs.

hulls; Pull up tubing to 900; Pumped 60 sks cement to circ cement at surf; pull tubing.

Hook up to casing. sq 35 sks cement in casing. Max 300 lbs. S.I. 200 lbs. Hook up to

8 5/8 s.p.; pumped 125 sks cement. Max 400 lbs. S.I. 200 lbs.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

FEB 13 1991

DATE 30716

INV. NO.

Signed Dennis L. Hamel

Dennis Hamel (TECHNICIAN)