

6 041150

3-14 15-147-00862-0860

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
SE SE NE SEC. 22, T 5 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

2970 feet from S section line

330 feet from E section line

Operator: Texaco Inc.
Name & Address: Box 779
Kingfisher, Okla. 73750

Lease Name B. O. Graham Well # 9

County Phillips 109.36

Well Total Depth 3365 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 13 3/8 feet 276 w/225 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____
Address Russell, Ks.

Company to plug at: Hour: 10:00 AM Day: 14 Month: Mar Year: 19 90

Plugging proposal received from Randall Mai

(company name) Texaco Inc. (phone) _____

were: 7" casing set at 3304' w/175 sks. Top perf at 3150'. T.O.C. 2372'.

Perf anhy at 1400' and base dakota at 900'. Holes in casing at 1602 - 2125.

Ordered 600 sks 65/35 poz 10% gel w/1/4# f.c. plus 10 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 14 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT R.I.H. w/tubing to 3186. Spot 90 bbls cement.

Pull tubing to 900' cir cement. Pumped in 7" casing 525 sks cement w/1/4# f.c. plus

7 sks hulls mixed in cement. Max 700#. S.I. 300# psi.

Pumped in 13 3/4" casing 75 sks cement w/1/4# f.c. plus 3 sks hulls mixed in cement.

Max 500#. S.I. 200# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

DATE 4-9-90
INV. NO. 22815
0407-1990
3-14

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis Hamel