

15-147-00861-00-00320P

6031455

API NUMBER 15- 1946

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NE SEC. 22, T 5 S, R 20 W/E

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name B. O. Graham Well # 6

Operator: Texaco Inc.

County Phillips 114.56

Name & Address Box 779

Well Total Depth 3525 feet

Kingfisher, Ok. 73750

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 279

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor OWS Well Service License Number

Address Palco, Ks.

Company to plug at: Hour: PM Day: 5 Month: Dec. Year: 19 90

Plugging proposal received from Goosetree

(company name) Texaco (phone)

were: 10 3/4 set at 279 w/150 sks. 5 1/2 set at 3493 w/150 sks. Perf 3239 - 3525.

Shots at 1630 and 1227. CIBP at 3190. Ran tubing to 3100. Order 400 sks 65/35 poz

10% gel 500 lbs. hulls 1/2 lb f.c. per sk.

OWS rig and water truck.

Halliburton Services. Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30PM Day: 5 Month: Dec Year: 19 90

ACTUAL PLUGGING REPORT Pump through tubing 250 sks cement blend.

To max psi 500 lbs. Close in psi 400 lbs. Sq 10 3/4 w/75 sks to max psi 500 lbs.

Close in psi 400 lbs. Plug complete.

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas
12-28-1990

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

DATE JAN 18 1991

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 30538

Carl Goodrow