

4-041631

11-18

15-147-00592-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 5-20-47

SW SW SE /4 SEC. 20, 05 S, 20 W
330 feet from S section line
2310 feet from E section line

Operator license# 5285

Lease P.V. States well # 1

Operator: Dane G. Hansen Trust

County Phillips

Address: P.O. Box 187
Logan, Kansas 67646

Well total depth 3592 feet ^{116.74}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 190 feet
w/200 sxs.cwc.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 18 Month: November Year: 94

Plugging proposal received from: Richard L. Wallgren Sr.

Company: Dane G. Hansen Trust Phone:

Were: 5 1/2" casing set @ 3580' w/150 sxs. cmt. Perf. @ 3409' - 3488'.
Anhy. @ 1730' - Dakota @ 1050' - W.L.M. @ 3450' - T.O.F. @ 1800'.
Squeeze @ 2665' - 2695' with 300 sxs.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
plus 12 sxs. gel.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:30P.M., Day: 18, Month: November, Year: 94

Actual plugging report: Perf. casing at 1730' and 1050'. Rig up cementers
to squeeze down 5 1/2" casing with 25 sxs. cement with 200# hulls,
followed with 12 sxs. gel, followed with 150 sxs. cement with 200# hulls.
Max. P.S.I. 400#. 10 3/4" S.P. Squeezed 50 sxs. cement with 100# hulls.
Max. P.S.I. 800#. S.I.P. 500#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X ^{INVOICED} observe the plugging. Dennis L. Hamel

DATE 12-6-94
INV. NO. 41820

(agent)
Form CP-2/3