

1-22-88
15-147-19130-00-03

6 031032

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1949

SW NE NE, SEC. 22, T 5 S, R 20 W/E

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name B.O. Graham Well # 11 SWD

Operator: Texaco Inc.

County Phillips 119.18

Name & Address Box 2 Star Route

Well Total Depth 3667 feet

Russell, Kansas 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well Gas Well Input Well SWD Well X U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Kansas

Company to plug at: Hour: AM Day: 22 Month: Jan Year: 19 88

Plugging proposal received from Earl Donaldson

(company name) Texaco (phone)

were: 8 5/8" 295' w/150 sks, 5 1/2" w/200 sks at 3512' w/liner 4 1/2 bottom w/50 sks

3501' - 3561'. D.H. 6'. Perfs shots at 1000' Dakota 50', Anhy at 1640' for block squeeze.

Order 150 sks ATL Cement Blend 65/35 Poz 10% Gel 2% Dicol 5 sks Hulls. Allied OWS Water

Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00PM Day: 22 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" w/75 sks Cmt. Blend 5 sks Hulls in with 25 sks Cmt

Blend. Max Psi 500#. Close in 200# Psi. Squeeze backside w/50 sks Cmt Blend. Max

Psi 300. Close in 200# Psi. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED serve this plugging.

DATE 2-15-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 19858 1-22-88

FEB 24 1988

MAR 24 1988