

Orig - State Corp. Comm. ✓

1 - B. A. Conner - 357 PB
1 - Mary Crump
1 - File

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-137-19022-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Norton SEC. 25 TWP. 5S RGE. 21 E/W
Location as in quarters or footage from lines:
990' FNL & 330' FEL NW/4

Lease Owner Phillips Petroleum Company
Lease Name Kemper Well No. 3
Office Address Box 287 Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 10/1/52
Application for plugging filed 4/14/81 Renewed 6/21/82
Plugging commenced June 29, 1982
Plugging completed June 29, 1982
Reason for abandonment of well or producing formation
Depleted Oil Well

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation LKC Depth to top 3464 bottom 3598 T.D. 3683

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
LKC	Oil	3464	3598	8 5/8	126	None
ARB.	Oil	3665	3683	5 1/2	3665	None
Non productive in LKC						

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Connected SUN OIL WELL Cementing to 5 1/2", test pumped and then pumped 3 sx hulls & 75 sx
cement w/ 3% CaCl & 6% Gel, followed by 14 sx gel and 150 sx cement w/ 6% gel & 3% CaCl
SIP 700#. Connected to 8-5/8" pumped 3/4 BW @ 700#. SI Bottom plug @ 2650', top Plug
at 1350' to surface.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing

STATE OF Kansas COUNTY OF Barton, ss.

Phillips Petroleum Company (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 287, Great Bend, KS 67530
(Address)



SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 82

Lisa M. Granger
Notary Public

My Commission expires: November 17, 1985

JUL 1 1982
CONSERVATION DIVISION
Wichita, Kansas
7-1-82