


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-137-30084-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

NORTON

County. Sec. 23 Twp. 5 Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner JOCELYN-VARN OIL CO.

Lease Name J. W. BAIRD Well No. 1

Office Address K F H BUILDING, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed SEPTEMBER 16 19 56

Application for plugging filed SEPTEMBER 16 - VERBAL 19 56

Application for plugging approved 19 _____

Plugging commenced SEPTEMBER 16 19 56

Plugging completed SEPTEMBER 16 19 56

Reason for abandonment of well or producing formation _____

DRY HOLE

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3627 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

**BOTTOM PLUG SET AT 195' WITH 1/2 SACKS HULLS AND 15 SACKS CEMENT.
TOP PLUG SET AT 40' WITH 1/2 SACKS HULLS AND 10 SACKS CEMENT.**

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY

Address 400 BROWN BUILDING, WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK
I, DAN J. KORNFELD (employee of contractor) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
DAN J. KORNFELD
400 BROWN BUILDING, WICHITA 2, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 24TH day of SEPTEMBER, 19 56

My commission expires June 7, 1960

Charlotte Stanley
Notary Public.

PLUGGING
FILE SEC. 23 T. 5 R. 21W
BOOK PAGE 100 LINE 36

RECEIVED
OCT 31 1956
10-3-56
CONSERVATION DIVISION
Wichita, Kansas

15-137-30084-00-00

LOG

COMPANY: JOCELYN-VARN OIL COMPANY

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: J. W. SAIRD No. 1

LOCATION: NW NW NE OF SEC. 23-5-21, NORTON COUNTY, KANSAS

COMMENCED: SEPTEMBER 7, 1956

COMPLETED: SEPTEMBER 16, 1956

ELEVATION: 2171' K.S.

0	TO	1400	SHALE AND SAND	TOPS:		
1400	TO	1760	SHALE			
1760	TO	1800	ANHYDRITE	HEEBNER	3330	MINUS 1159
1800	TO	2600	SHALE AND SHELLS	TORONTO	3356	MINUS 1165
2600	TO	2950	SHALE AND LIME	LANING KANSAS CITY	3371	MINUS 1200
2950	TO	3075	SHALE AND SHELLS	ARBUCKLE	3510	MINUS 1439
3075	TO	3407	SHALE AND LIME	REGAN	3524	MINUS 1453
3407	TO	3627	LIME			
3627			R.T.D.			

DRY AND ABANDONED - RAN ELECTRIC LOG

CASING: RAN 200 FT. OF 8 5/8" AND CEMENTED WITH 115 BAGS CEMENT.

D.S.T. #1 3505-3511 OPEN 30 MIN. WEAK BLOW FOR 3 MIN. RECOVERED 15 FT. GAS CUT MUD, SPECKS OF OIL. NO PRESSURE.

D.S.T. #2 3509-3516 OPEN 1 HR. WEAK BLOW FOR 18 MIN. RECOVERED 35' OF FLUID WITH 5 FT. OF OIL, 30 FT. MUD. NO WATER. NO INITIAL OR FLOW PRESSURE.

D.S.T. #3 3512-3527 OPEN 1 HR. FAIR BLOW FULL HOUR. RECOVERED 135 FT. FLUID 10 FT. OIL, 125 FT. WATERY MUD, SLIGHTLY SALTY. NO INITIAL OR FLOW PRESSURE. S.H.P. 770 LBS. 20 MINUTES.

CERTIFICATION

I, DAN J. KORNFIELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE J. W. SAIRD No. 1, NW NW NE OF SEC. 23-5-21, NORTON COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
DAN J. KORNFIELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 24TH DAY OF SEPTEMBER, 1956.

Lucille Varn
NOTARY PUBLIC

My Commission Expires Oct. 21, 1958

PLUGGING
FILE SEC 23 T 5 R 21W
BOOK PAGE 100 LINE 36