

3 022657

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:30A.M. Day: 29 Month: 10 2004Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELT 1000' THAT HADBEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE ASMUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All _____ Part ☒ None _____

TECHNICIAN

Operations Completed: Hour: 2:00P.M. Day: 29 Month: 10 2004Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 8" ANNULUSTO 400'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATEDFROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENTWAS FILLED FROM SURFACE. 136 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO. 70) (THIS WAS WELL NO. W-12 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANBuKCC
BEM
12/13/04
RBDMS
Per
FootagesAPI NUMBER
SE SW NW
NW, NW, SW 1/415-207-19454-00-00
CONTROL NO. 20040041

Sec/Twp/Rge S.34-T.26S.-R.16E.

2775 feet from south section line

4450 feet from east section line

Lease/Well# APT NO. W-12

County WOODSON

Well Total Depth 1000' feet

Production Pipe: 2" Size Feet 1000'

Surface Casing: 8" Size Feet 20'

RECEIVED
NOV 08 2004
KCC-WICHITA