

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20557-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 35-14S-19W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: YOUNKER Well #: 1
County: ELLIS Total Vertical Depth: 3725 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3720 w/135 sxs cmt
SURF Size: 8.625 feet: 1342 w/650 sxs cmt

Well Type: EOR UIC Docket No: E23540.1 Date/Time to Plug: 12/02/2004 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
CIBP at 3650'. WLTD at 3350'.
Squeezed from 3650' to 3435' w/300 sxs cement on September 2004.
Attempted to drill out - got outside of the casing - decided to P&A with rig over the hole.
This well originally was an oil well. Later converted to injector.
Operator then produced the well. Operator did not cancel the docket.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2004 5:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Cut casing loose at 2400'.
Pulled up to 2000' - mixed and pumped 110 sxs cement with 200# hulls.
Pulled up to 1400' - spotted 40 sxs cement with 100# hulls.
Pulled up to 550' - spotted 30 sxs cement with 100# hulls.
Pulled up to 200' - circulated cement with 60 sxs cement.
POOH. Hole full of cement.

Perfs:
RECEIVED
DEC 13 2004
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 12-13-04
2005060924

DEC 09 2004

ENERGY SOURCES, INC.
4413 82ND ST
LUBBOCK, TX 79424

"OWWO"
#1 YOUNKER

35-14-19W
NW SW NE

CONTR UNKNOWN

CTY ELLIS

GEOLOGICAL MARVIN SULLIVAN

FIELD ANTONINO SOUTH


ELV 2101 KB SPD NA

CARD ISSUED 5/23/85

WIW

API 15-051-20.557

LKC 3424-3576 OA



LOG	Type	Depth/Datum
ANH		1345+ 756
TOP		3101-1000
HEEB		3354-1253
TOR		3377-1276
LANS		3401-1300
ARB		3713-1612
PBTD		3640-1539
RTD		3725-1624

OLD INFO: OPERATOR WAS BEACON RESOURCES CORPORATION, #1 YOUNKER, SPD 12/29/69, SET 8 5/8 " 1342, 5 1/2 " 3720, COMP AS P 70 B0 & 57 BWP0, ARB 3720-25 (GR 38.4") (CARD ISSUED 4/23/70), CONTR: L. J. DREILING & SONS, GEOL: GLEN THRASHER

DST (1) 3420-33 (LANS) / 30-30-30-30, GTS/20", NO GAUGE, REC 1500' GSY OIL, SIP 848-848#, FP 88-440#

DST (2) 3442-60 (LANS) / 30-30-30-30, 1920' GIP, REC 120' HOCM, 540' FRGY OIL, 180' W, SIP 992-992#, FP 72-530#

DST (3) 3529-50 (LANS) / 30-30-30-30, REC 20' M, SIP 56-64#, FP 32-32#

DST (4) 3554-70 (LANS) / 30-30-30-30, REC 5' GCM, SIP 40-32#, FP 32-32#

DST (5) 3578-3600 (LANS) / 30-30-30-30, GTS/40", NO GAUGE, REC 60' HO & GCM, 840' OIL, SIP 1221-1221#, FP 48-272#

DST (6) 3691-3717 (PENN,ARB) / 30-30-30-30, REC 10' SOCM, SIP 40-56#, FP 32-40#

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

MADE IN