

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23408-00-00
Spot: E2SW Sec/Twnshp/Rge: 21-9S-19W
1270 feet from S Section Line, 1825 feet from W Section Line
Lease Name: MONGEAU Well #: 1
County: ROOKS Total Vertical Depth: 3640 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3639 w/125 sxs cmt
SURF Size: 8.625 feet: 231 w/150 sxs cmt

11830

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2004 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2004 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded off casing to 3250' and topped with 5 sxs cement using a dump bailer.
Cut casing loose at 2400'.
Pulled up to 2100' - mixed and pumped 120 sxs cement with 300# hulls.
Pulled up to 1600' - spotted 40 sxs cement with 100# hulls.
Pulled up to 800' - spotted 40 sxs cement with 100# hulls.
Pulled up to 200' - circulated cement with 50 sxs cement.
POOH. Hole full of cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

RECEIVED
DEC 13 2004
KCC WICHITA

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICE

DATE 12/13/04
INV. NO. 2005060926

DEC 10 2004