

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00511-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas
12-6-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Bailey "A" Well No. 3

Location NE SE NE Sec. 30 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3665'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:45 P Day 3 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3665' 8 5/8 csg set at 207' cwc 250 sk.

5 1/2 csg set at 3665' cw 100 sk cmt.

5 1/2 csg PBTB 3647' with perf. (3641-3644)

Filled 5 1/2 csg W/sd (3625-3647) Dumped 5 sk cmt W/dump bailer. (3590-3625)

Cutoff and recovered 600' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel & water W/100 lbs hulls -released

plug and pumped 100 sk 50-50 poz W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 12/6/71
INV. NO. 4768-W