

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00512-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas
12-6-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Bailey "A" Well No. 4
Location NW SE NW Sec. 30 Twp. 5 Rge. (E) (W) 20
County Phillips Total Depth 3653'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 4:30 P Day 3 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3653' 8 5/8 csg set at 200' cwc 250 sk.

5 1/2 csg set at 3650' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3640-3653) Dumped 5 sk cmt W/dump bailer. (3600-3640)

Recovered 515' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel & water W/100 lbs hulls -
released plug and pumped 100 sk 50-50 poz W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12/6/71

INV. NO. 4769-W