

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00519-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1971
CONSERVATION DIVISION
Wichita, Kansas
7-12-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name _____ States "B" Well No. 7
Location NE SW NW Sec. 30 Twp. 5 Rge. (E) (W) 20
County Phillips Total Depth 3654'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas License No. 436
Operation Completed: Hour 12:30 P Day 9 Month 7 Year 1971

The above well was plugged as follows:

Total Depth 3654' 8 5/8 csg set at 198' cwc 250 sk.
5 1/2 csg set at 3648' cw 150 sk cmt.
Filled 5 1/2 csg W/sd (3630-3654) Dumped 5 sk cmt W/dump bailer. (3600-3630)
Cutoff and recovered 888' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls (800-TD) -70 sk poz 6%
(600-800) -10 sk gel (200-400) -50 sk poz 6% (0-200)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 7/12/71
INV. NO. 3973-W