

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00593-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas
12-6-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Bailey "A" Well No. 2
Location SW SW NE Sec. 30 Twp. 5 Rge. (E) (W) 20
County Phi;;ips Total Depth 3633'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 3 P Day 3 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3633' 8 5/8 csg set at 197' cwc 200 sks.
5 1/2 csg set at 3616' cw 150 sk cmt
Filled 5 1/2 csg W/sd (3600-3633) Dumped 5 sk cmt W/dump bailer. (3560-3600)
Recovered 600' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel & water W/100 lbs hulls -released
plug and pumped 100 sk 50-50 poz W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/6/71
INV. NO. 4767-W

Signed: [Signature]
Well Plugging Supervisor