

KANSAS

*JP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00594-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
12-6-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company  
Complete Address Box 553 Russell, Kansas 67665  
Lease Name Bailey "A" Well No. 1  
Location SW SE NE Sec. 30 Twp. 5 Rge. (E) (W) 20  
County Phillips Total Depth 3657'  
Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Knight Casing Pulling  
Address Box 405 Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 11:30 A Day 3 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3657' 8 5/8 csg set at 156' cwc 100 sk.

5 1/2 csg set at 3657' cw 100 sk cmt.

5 1/2 csg PBTD 3562' with perf. (3370-3435)

Set 5 1/2 wood plug at 3350' -poured 20' sd -dumped 5 sk cmt W/dump bailer. (3300-3350)

Shot off and recovered 616' of 5 1/2 csg.

Pulled 5 1/2 csg to 550' -circulated 20 sk gel & water to surface -displaced 50 sk  
50-50 poz 6%.

Pulled 5 1/2 csg to 155' -circulated 50 sk 50-50 poz 6% to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Geo. J. Murray*  
Well Plugging Supervisor

DATE 12/6/71

INV. NO. 4766-w