

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00275-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1962

CONSERVATION DIVISION
Wichita, Kansas

7-24-62

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name J. O. Farmer Inc

Complete Address: Russell, Kansas

Lease Name Wiltrout Well No. 1

Location SW NW SE Sec. 24 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3616

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4PM Day 21 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 157' circulated with cement - 5 1/2" 3607' cement to 3174' survey -
 PB 3402' - perf 3367'.
 Sand back to 3300', set 4 sax cement - pulled 3160' 5 1/2" to 550', circulated
 hole with heavy pit mud, displaced 20 sax cement through 5 1/2" at 550', heavy
 mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to
 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/27/62
INV. NO. 5438-W

Signed: Edna Perry
Well Plugging Supervisor