

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-30068-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1974
CONSERVATION DIVISION
Wichita, Kansas
10-7-74

Operator's Full Name Leland R. Baird,
Complete Address Logan, Kansas.
Lease Name Baird Fee Well No. 1
Location CS Line-NE-NE Sec. 23 Twp. 5 Rge. (E) (W) 21
County Norton Total Depth 3611'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas License No. 399
Operation Completed: Hour 6:00 PM Day 2 Month 10 Year 1974

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.
3607'--4 1/2" Production casing cemented on bottom with 75 Sx. (Open Hole Completion)
Top of Dakota section @ 775.
Sanded well back to 3590' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing
(2420') and squeezed well initially with 5 sacks hulls and 11 sacks gel followed with
110 Cu. Ft. cement from 1000' to 675' then 11 sacks gel from 675' to 215' and followed
with 30 Cu. Ft. cement from 215' to 140' then 3 sacks gel from 140' to 20' and finally
10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-500%. Final
Shut-in Pressure-200%. (Mudding & Cementing by Allied Cmtg. Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. J. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/8/74
INV. NO. 51-W