

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

SEP 21 1973

CONSERVATION DIVISION
Wichita, Kansas

9-21-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-137-19017-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Kemper Well No. 2

Location NE-NW-SE Sec. 23 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3628'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling,

Address Box # 176, Chase, Kansas. License No. 683

Operation Completed: Hour 10:00 AM Day 19 Month 9 Year 1973

The above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 160 Sx.
3624'--5 1/2" Production casing, cemented on bottom. Open Hole Completion.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1100') and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed
with 110 Cu. Ft. cement from 1025' to 700' then 12 sacks gel from 700' to 220' and
followed with 30 Cu. Ft. cement from 220' to 145' then 3 sacks gel from 145' to 25'
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-
-300#. FSIP-100#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

DATE 9-21-73

Signed: N. S. Nichols
Well Plugging Supervisor

INV. NO. 7946-00