

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-137-00693-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 17-10,

LOCATION NE SE NE

SEC. 25 TWP. 5 RGE. 21

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. C-1 Lease _____ States _____

Operator Cities Service Co ^{Oil} Address Great Bend, Kans

Field _____ County Norton

Total Depth 3689 Feet.

Plugging Contractor G. E. Shull

Plugging Contractor's License No. 8

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement - 5 1/2" at 3689' with
150 sax cement behind - squeezed with 150 and 200 sax cement.
Lane Wells plugs to 3495', perforated at 3425'.
Filled with sand to 3400', set 4 sax cement with dump bailer,
pulled 1980' 5 1/2' - filled hole with mud to 220', set rock and
15 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

District Conservation Agent

Date 4-1-54

PLUGGING
FILE SEC 25 T 5 R 21W
BOOK PAGE 17 LINE 10

4-5-54

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS