

SR

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

~~15-137-00229-00-01~~
15-137-00092-00-01
RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas
6-10-71

Operator's Full Name Will P. Ash.
Complete Address 230 Sutton Place, Wichita, Kansas.
Lease Name Kemper Well No. 1
Location SW-SW-NE Sec. 25 Twp. 5 Rge. (E) (W) 21
County Norton Total Depth 3720'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated WASHDOWN--D&A
Plugging Contractor Sage Drilling Company, Incorporated,
Address 500 Bitting Building, Wichita, Mo. License No.
Operation Completed: Hour 11:30 PM Day 3 Month 6 Year 1971

The above well was plugged as follows:

179'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 100 Sx. cement thru
DP from 925' to 600'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from 215'
to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dickah
Well Plugging Supervisor

DATE 6-10-71

INV. NO. 3839-W