

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-19018-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1961

CONSERVATION DIVISION  
Wichita, Kansas

8-4-61

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Norton

Location: SE SW SW Sec. 23 Twp. 5 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 21

Name of Field: \_\_\_\_\_ Total Depth: 3631

I have this date completed supervision of plugging of:

Lease Name: Shugart Cshughart Well No. 1

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kansas

Plugging Contractor: same & Sun Cementing Co

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1PM Day 2 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 213' circulated with cement - 5 1/2" 3624' with 100 sax cement.

Set 6 sax cement on bottom with dump bailer, pulled 1300' 5 1/2" to 500'.

circulated hole with heavy mud through 5 1/2" at 500', displaced 20 sax

cement through 5 1/2" at 500', heavy mud to 160', displaced 20 sax cement

through 5 1/2" ay 160', heavy mud to 35', cemented from 35 to 0'.

Mudding and cementing by Sun Cementing Co.

Signed: Edon Perry  
Conservation Division Agent

Reviewed: Harold Harris  
Field Supervisor

Remarks:

INVOICED

DATE 8/18/61

INV. NO. 3619-w