

K KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-137-00537-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1965
12-28-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name Kemper Well No. 3

Location NW-SW-SE Sec. 23 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3658

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00PM Day 18 Month 12 Year 1965

The Above well was plugged as follows:

191'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3641'--5 1/2" Production casing cemented with 100 Sx. (Open hole completion)

Sanded well back to 3620' and set 5 Sx. cement with dump bailer.

Shot and pulled 5 1/2" to 600' and attempted to circulate heavy gel mud.
pumped in 5 Sx. gel, no circulation, 200# pressure. Pulled 5 1/2" to 500'
and circulated heavy gel mud. (Used 15 Sx. gel). Pulled 5 1/2" to 440' and
displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 180' and displaced 20 Sx.
cement thru 5 1/2". Pulled 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom
of cellar.

(Recovered 2020' 5 1/2" Casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 12/28/65

INV. NO. 2489-W