

KANSAS

X
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00310-06-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1970
CONSERVATION DIVISION
Wichita, Kansas
9-15-70

Operator's Full Name Phillips Petroleum Company,

Complete Address Box #287, Great Bend, Kansas.

Lease Name Kemper Well No. 5

Location CSW-SW-NE Sec. 23 Twp. 5 Rge. (E) (W)21

County Norton Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 4:45 PM Day 11 Month 9 Year 1970

The above well was plugged as follows:

399'--10 3/4" Surface casing, cement circulated.
3623'--7" OD Production casing cemented on bottom with 150 Sx. 7" had been squeezed thru perforations @ 2000' & 2500' with 178 Sx. cement.
Ran wire line to establish bottom (3638'). Sanded back to 3600' and set 5 Sx. cement with dump bailer. Attempted to pull 7" was only able to back off 3 joints @ 95'.
Squeezed well initially with 5 sacks hulls and followed with 20 sacks gel then 165 Sx. cement and followed with 25 sacks gel and finally 10 Sx. cement. Maximum pump-in pressure 600#. Final shut-in pressure- 400#. (Mudding & cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Dickels*
Well Plugging Supervisor

DATE 9-15-70

INV. NO. 2536-4