

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-147-20,358-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name K. R. M. Petroleum Corporation

Complete Address 817 17th St., Suite #820, Denver, Colorado 80202

Lease Name Patton Well No. #1-9

Location SW NE Sec. 9 Twp. 5 N Rge. 17 E (East) (West)

County Phillips Total Depth 3562'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated _____

Plugging Contractor Kandrilco Ltd.

Address 555 N. Woodlawn Bldg. 1, Suite #207, Wichita, Ks. License No. _____

Operation Completed: Hour: 12:05AM Day: 6th Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All Part None X

The above well was plugged as follows:

8 5/8"-202' s.p. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated with 10 sacks of cement in rat hole and 5 sacks in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1981
12-14-81

CONSERVATION DIVISION

Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 12-18
INV. NO. 9064-u