

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-20-1959
OCT 20 1959

CONSERVATION DIVISION
Wichita, Kansas

15-147-00623-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 4-8 County: Phillips

Location: SE NW NE Sec. 22 Twp. 5 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3615

I have this date completed supervision of plugging of:

Lease Name: De Muth Well No. 3

Operator's Full Name: Colorado Oil & Gas

Complete Address: Box 1030 Wichita, Kans

Plugging Contractor: Knight Casing Pulling Co

Address: Great Bend, Kans License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10 AM Day 15 Month 10 Year 59

The above well was plugged as follows:

8 5/8" 277' circulated with cement - 4 1/2" 3615' with 120 sax cement.

PB 3599' , perforated 3536'.

Filled with sand to 3520', set 3 sax cement with dump bailer, pulled

1522' 4 1/2" to 550', circulated hole with heavy mud (Gel), displaced 20 sax

cement through 4 1/2" at 550', heavy mud to 180', displaced 20 sax cement

through drill pipe at 180', heavy mud to 35', set bridge and 10 sax cement

to bottom cellar.

Mudding and cementing by Knight Cos pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/12/60
INV. NO. 375-w