

15-147-19124-00-01

Form CP-3  
Rev. 6-4-68

*Y*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
02-08-1971  
FEB 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Speeter Pipe & Supply, Inc.

Complete Address Box 169 Russell, Kansas 67665

Lease Name Demuth Well No. 1

Location NE SW NE Sec. 22 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3604

Abandoned Oil Well XXX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Lynch Casing Pulling Co.

Address Great Bend, Kansas License No. 457

Operation Completed: Hour 12:30P Day 2 Month 2 Year 1970

The above well was plugged as follows:

Total Depth 3604' 8 5/8 csg set at 242' cwc

5 1/2 csg set at 3544' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3530-3544') Dumped 5 sk cmt W/dump bailer. (3500-3530)

Recovered 1000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 18 sk gel W/5 sk hulls - 70 sk 50-50 poz 6% -

10 sk gel - release plug and pumped 50 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-8-71

INV. NO. 3313-W

Signed: Leo J. Messing  
Well Plugging Supervisor