

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-00708-00-00

FILE NO. 110-10
LOCATION SW SE SW
SEC. 22 TWP. 5 RGE. 20

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-1 Lease De Muth

Operator Cities Service Co Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3024 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3619' with
150 sax cement behind - Lane Wells plugs to 3593' - top
perforations at 3511'.

Filled with sand to 3500', set 4 sax cement with dump bailer,
pulled 2812' 5 1/2", filled hole with mud to 200', set rock and 15
sax cement, filled with mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1951
CONSERVATION DIVISION
Wichita, Kansas

John J. [Signature]
District Conservation Agent
Date 9-29-51