

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-00704-00-00

FILE NO. \_\_\_\_\_

LOCATION NE-SW-SE

SEC. 20 TWP. 5 RGE. 20-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease P.V. States

Operator D.G. Hansen Address Logan - Kansas

Field D.G. Hansen County Phillips

Total Depth 3632 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 210ft - Cemented with Cement  
5 1/2" casing set at 3633 ft & cemented with 150 sacks of Cement.  
Casing Prepared & Lined tested - Top Perforations 3375ft.  
Filled hole back to 3375ft - Put in 5 sacks cement  
at 3375ft - Shot off & recovered 1300ft of 5 1/2" casing  
Filled with mud to 210ft - Plug & 15 sacks cement  
at 210ft - Surface Plug 25ft below the surface &  
10 sacks cement - Filling hole to surface

Patterson & Son -  
Pipe Pullers & Pluggers.

C. H. Stough  
District Conservation Agent

Date 10-22-47

**PLUGGING**  
FILE SEC 20 T 5 R 20  
BOOK PAGE 14 LINE 35

10-22-1947