

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-147-00618-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1974
02-01-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dane G. Hansen Trust
Complete Address Logan, Kansas 67646
Lease Name P. V. States Well No. 2
Location SW SE SE Sec. 20 Twp. 5 Rge. (E) (W) 20
County Phillips Total Depth 3664'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas License No. 399
Operation Completed: Hour 1:45 P Day 29 Month 1 Year 1974

The above well was plugged as follows:

Total Depth 3664' 8 5/8 csg set at 267' ewe 150 sk.
5 1/2 csg set at 3647' ew 150 sk cem.
5 1/2 csg perf. (3389-3496)
Filled 5 1/2 csg W/sd (3630-3664) dumped 4 sk emt W/dump bailer. (3600-3630)
Set 5 1/2 wood plug at 3350' -poured 10' sd -dumped 3 sk emt W/dump bailer. (3315-3350)
Cutoff and recovered 1330' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls -70 sk 50-50 pez 6% gel-
15 sk gel & water -released 8 5/8 plug and pumped 50 sk 50-50 pez 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/1/74
INV. NO. 8479-W

State of Kansas



15-147-00618-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 17, 1974 RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1974

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING AUTHORITY

Well No.	2
Lease	P. V. States
Description	SW SE SE Sec. 20-5S-20W
County	Phillips
Total Depth	3658'
Plugging Contractor	SW Casing Pulling Company


Dane G. Hansen Trust
Logan, Kansas 67646

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Leo Massey, P. O. Box 582, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above named well.