

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-147-20011-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1967
09-13-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Schreiner Petroleum

Complete Address: 548 Petroleum Bldg. Wichita, Kansas

Lease Name Mary Lamb Well No. 1

Location SE SW NE Sec. 21 Twp. 5 Rge. 20 (E) (W) X

County Phillips Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones Inc.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 5:30 ^P Day 11 Month 9 Year 1967

The Above well was plugged as follows:

RTD 3640' 8 #18 csg set at 225' cwc 225 sc.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/13/67
INV. NO. 6318-W

Signed: [Signature]
Well Plugging Supervisor