

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-147-00859-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 109-38

LOCATION SW SE SW

SEC. 20 TWP. 5 RGE. 20

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hansen

Operator Skelly Oil Co Address Hutchinson, Russell, Kans

Field Logan County Phillips

Total Depth 3618 Feet.

(Describe briefly the manner in which the well was plugged)

5 1/2" at 3612' - 10" at 235' circulated with cement.

Filled with chat to 3600', set 4 sax cement with dump bailer,

~~mixed~~ shot 5 1/2" at 2455', pumped hole full mud, trying to

circulate pipe, pulled 890' 5 1/2", filled hole with mud to

230', set rock bridge and 25 sax cement, filled with mud to

35', set rock bridge and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC. 20 T. 5 R. 20
BOOK PAGE 109 LINE 38

E. J. ...

District Conservation Agent

Date

9-19-51
RECEIVED
STATE CORPORATION COMMISSION
09-25-1951
SEP 25 1951

CONSERVATION DIVISION
Wichita, Kansas