

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-00705-00-00

FILE NO. _____

LOCATION NE-SF-SE

SEC. 20 TWP. 5 RGE. 20 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease P.V. States

Operator A.G. Hansen Address Togan - Kansas

Field _____ County Phillips

Total Depth 3651 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 216 ft - Circulated with Cement
5/8" casing was set in this well at 3625 ft & cemented
& tested in place at 3360 ft. Top Perforations at 3366 ft
Filled hole back to 3350 ft with sand - 9.5 sacks of
Cement 3350 ft - Shot off & recovered 2400 lb of 5/8" casing
Filled with mud to 216 ft. Set Plug & 15 sacks cement
at 216 ft - Mud to within 30 ft of the surface - Plug
& 10 sacks cement.

Patterson & Son
Pipe Pullers & Pluggers

C. W. Stough
District Conservation Agent

Date 10-30-47

PLUGGING
FILE SEC 20 T 5 R 20 W
BOOK PAGE 144 LINE 70

1947
11-01-1947