

15-147-20217-00-00

R

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 12 1976
03-12-1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 147 - 20, 217 (of this well)

Operator's Full Name Cities Service Oil Co.

Complete Address 700 Sutton Place Bldg., 209 E. William, Wichita, Kansas

Lease Name Demuth "A" Well No. 1

Location C N/2 SE NW Sec. 22 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3690'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Helberg Drlg.

Address Morland, Kansas License No.

Operation Completed: Hour 11:30 P Day 9 Month 3 Year 1976

The above well was plugged as follows:
RTD 3690' 8 5/8 csg set 209' cwc 160 sx. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3-12-76
INV. NO. 2886-W

Signed: [Signature]
Well Plugging Supervisor