

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-20.168-00-01

LEASE NAME Hansen "C"

WELL NUMBER 7

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days.

3960 ft. from S Section Line

2640 ft. from E Section Line

SEC. 23 TWP. 05 RGE. 20 or (W)

COUNTY Phillips

Date Well Completed 02/18/74

Plugging Commenced 11/14/96

Plugging Completed 11/14/96

LEASE OPERATOR OXY USA Inc.

ADDRESS P.O. Box 300; Tulsa, OK 74102-0300

PHONE # (918) 561-2211 OPERATOR'S LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply)

The plugging proposal was approved on October 22, 1996 (date)

by Dennis L. Hamel

Is ACO-1 file? Yes If not, is well log attached? _____

Producing Formation Lower Arbuckle Depth to Top 3597' Bottom 3605' T.D. 3724'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
Lower Arbuckle	Oil	3597'	3605'	8-5/8	218'	0
Gorham	Oil	3540'	3544'	5-1/2	3722'	0
Lansing / LKC	Oil	3262'	3359'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Dug out csg. and orange peeled 5-1/2" to 8-5/8" csg. RIH w/ Howco and perfed @ 1723' and 1100'. RIH w/ 2-3/8" to 3500'. RU Howco and pumped 65 sxs MIDCON 2 w/ 2% C.C. and 200# hulls. POOH w/ 48 jts. to 2000'. Pumped 65 sxs cmt. and 200# hulls. POOH w/ 48 jts. to 500'. Pumped 40 sxs cmt and circ. to surface. POOH w/ rest of tbg. Pumped 30 sxs and S.I.P. 300#. (continued on back)

Name of Plugging Contractor Halliburton Energy Services License No. 5287

Address 1102 E. 8th St.; Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Kansas COUNTY OF Rooks, ss.

Kenneth R. Curry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Drawer D; Plainville, KS 67663

FEB 18 1997
02-18-1997
SUBSCRIBED AND SWORN TO before me this 14 day of February, 1997
CONSERVATION DIVISION
WICHITA, KS

[Signature]
Notary Public

My Commission Expires: May 20, 2000



Additional plugging record information for Hansen "C" #7

Hooked onto backside and pumped 5 sxs down. (Well was DV'ed). S.I.P. 500#. Closed in. RDMO. Following day checked well and it still had pressure. Dug out csg. and cut off 6' below ground level.