


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Phillips County. Sec. 21 Twp. 5 Rge. 20 (NE) (W)  
Location as "NE/CNW%SW%" or footage from lines. C NE NE NW  
Lease Owner Helmerich & Payne, Inc.  
Lease Name Mary Lamb Well No. 1  
Office Address Box 558, Garden City, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-5-65 19  
Application for plugging filed 12-5-65 19  
Application for plugging approved 12-5-65 19  
Plugging commenced 12-5-65 19  
Plugging completed 12-5-65 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Lieker Victoria, Kansas  
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3666 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	surface casing	4'	217'	8-5/8"	217'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3666' to 540' Heavy Rotary Mud  
540' to 480' Plug & 20 sacks cement  
480' to 200' Heavy Rotary Mud  
200' to 140' Plug & 25 sacks cement  
140' to 40' Heavy Rotary Mud  
40' to 4' Plug & 10 sacks cement  
4' to 0 cellar

DEC 16 1965  
12-18-1965

Plugging Completed 12:15 PM 12-5-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Co.  
Address Union Center Bldg, Wichita, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.  
C. A. Richter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Richter  
Box 558, Garden City, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 8 day of December, 19 65

My commission expires July 1968

Robert N. Boyd  
Robert N. Boyd Notary Public.

# WELL LOG

15-147-30101-00-00

COMPANY Helmerich & Payne, Inc.

SEC. 21 T. 5S R. 20W

FARM LAMB

NO. 1

LOC. NE NE NW

RIG. NO. 11

TOTAL DEPTH 3666

COUNTRY Phillips  
KANSAS


COMM. 11-27-65

COMP. 12-5-65

SHOT OR TREATED

CONTRACTOR Murfin Drilling Company

ISSUED



### CASING

20	10
15	8 5/8" 218' w/225 sacks
12	6
13	5

ELEVATION 2163 KB

PRODUCTION D&A

FIGURES INDICATE BOTTOM OF FORMATIONS

218 Shale  
 1620 Shale & Sand  
 1716 Shale  
 1782 Anhydrite  
 2175 Shale  
 2300 Shale & Shells  
 3185 Shale & Lime  
 3298 Lime & Shale  
 3301 Heebner  
 3325 Lime & Shale  
 3615 Lime  
 3627 Conglomerate  
 3666 Arbuckle  
 3666 RTD

RECEIVED  
STATE OIL AND GAS COMMISSION

JAN 24 1966

OK'd by [unclear] & [unclear]  
[unclear], Kansas

3666  
 2163  
 -1503  
 -----  
 2163  
 3627  
 2163  
 -----  
 464

State of KANSAS  
 County of SEDGWICK } ss:

I, C. Robert Buford of the Murfin Drilling Company  
 upon oath state that the above and foregoing is a true and correct copy of the log of the LAMB #1 well.

MURFIN DRILLING COMPANY  
 By: C. Robert Buford  
 C. Robert Buford

Subscribed and sworn to before me this 16th day of December 19 65

My Commission Expires: ADELA MIZENER, Notary Public  
 My commission expires November 5, 1966

Adela Mizener  
 NOTARY PUBLIC