


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

PHILLIPS County. Sec. 21 Twp. 5S Rge. (E) 20 (W)
Location as "NE/CNWxSWx" or footage from lines SE SW NE
Lease Owner SCHREINER PETROLEUM
Lease Name MARY LAMB Well No. 1
Office Address 548 PETROLEUM BUILDING, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPTEMBER 11 19 67
Application for plugging filed (PHONE - 9/11/67) SEPTEMBER 14 19 67
Application for plugging approved SEPTEMBER 11 19 67
Plugging commenced SEPTEMBER 11 19 67
Plugging completed SEPTEMBER 11 19 67
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LES MASSEY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	229	8 5/8	229	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 800 FEET. SET FIRST PLUG AT 800 FEET WITH 100 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 210 FEET. SET SECOND PLUG AT 210 FEET WITH 25 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET THIRD PLUG AT 40 FEET WITH ONE-HALF SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE WITH TWO SACKS CEMENT. USED GLOBE CEMENTING PUMP TRUCK AND PUMPED CEMENT THRU DRILL PIPE. JOB COMPLETE AT 5:30 PM ON SEPTEMBER 11, 1967.

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1967
09-15-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 SUTTON PLACE - WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of SEPTEMBER, 19 67

My commission expires JUNE 28, 1970

Jean S. Taylor
JEAN S. TAYLOR Notary Public.