

LEASE NAME States

WELL NUMBER #1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 20 TWP. 5 RGE. 20 (X) or (W)

COUNTY Phillips

Date Well Completed 5/16/47

Plugging Commenced 10:15 A.M. 11/18/94

Plugging Completed 12:15 P.M. 11/18/94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well D&A *OK*

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 18, 1994 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Reagan Depth to Top 3590 Bottom 3592 T.D. 3592

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	190'	None
				5 1/2"	3580'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 5 1/2" csg. - Mixed 25 sx cement w/200# hulls, 12 sx Gel, 150 sx cement w/200# hulls @ 700# Max PSI. Shut in @ 300#
 10 3/4" - Backside mixed 70 sx cement w/100# hulls @ 500# Max PSI. Shut in @ 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.


Dane G. Bales, Manager (Employee of Operator) or Operator of

above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Dane G. Bales*


(Address) Dane G. Bales
 P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1994



Betty Jane Bittel
 Betty Jane Bittel Notary Public

My Commission Expires: July 17, 1996.



RECEIVED
NOV 21 1947

15-147-00592-00-00

DRILLER'S LOG

D. G. Hansen
Logan, Kansas

SW SW SE
Sec. 20-59-20W
Phillips County, Kans.

States "B" No. 1

Comm.: 5-6-47; Comp.: 5-16-47

Elevation:

Contractor: Glenn Peel Drig. Co., Inc.
Hoisington, Kansas

Productions:

Casing: 10 3/4" OD 189 ft. Cem.
5 1/2" OD 3583 ft. Cem.

Figures indicate bottom of formations

0 -	92	Sand
	155	Sandy shale
	190	Shale
	485	Shale and shells
	607	Shale
	740	Shale and shells
	812	Sand and shale
	1055	Sand
	1422	Sand and shale
	1703	Shale and shells
	1740	Anhydrite
	2069	Shale and shells
	2645	Shale and lime
	2720	Lime
	2795	Shale and shells
	2810-	Lime and shale
	2985	Lime and shale
	3170	Shale and lime
	3225	Lime
	3235	Shale and shells
	3298	Shale and lime
	3585	Lime
	3585	Rotary Total Depth.

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1994
DIVISION
WICHITA, KANSAS