

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399
Phone: (785) 398-2270 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/26/04 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4481' Bottom: 4482' T.D. 4550'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-083-20765-00-00
Lease Name: Housman
Well Number: 3
Spot Location (QQQQ): NE-SW-SW *KCC BEM 12/14/04 RBDMS CP2/3 GPS*
990-995 Feet from North / South Section Line
990-4234 Feet from East / West Section Line
Sec. 2 Twp. 23 S. R. 22 East West
County: Hodgeman
Date Well Completed: 9/18/80
Plugging Commenced: 11/26/04
Plugging Completed: 11/26/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	oil/water	4481'	4482'	8 5/8"	1129'	None
				5 1/2"	4542'	1983'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off bottom to 3920' with 5 sacks of cement on top, pulled stretch and shot off casing @ 1983". Pulled casing up to 1160' and mixed 15 sacks of gel and 100 sacks of cement (60/40 poz, 6% gel) and balance plug @ 1160'. Pulled casing to 550' and mixed 50 sacks of cement and placed plug, pulled casing to 40' and mixed 20 sacks cement and place plug, pulled out and topped off 8 5/8", well plugged.


Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: N. Highway 283, Ness City, KS 67560
Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 6th day of December, 20 04
Bernice Moore My Commission Expires: 2/17/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
DEC 10 2004
KCC WICHITA