

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22255-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 24-13S-14W  
330 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: KRUG C Well #: 1  
County: RUSSELL Total Vertical Depth: 3295 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

CIBP Size: feet: 2930  
PROD Size: 5.5 feet: 3289 150 SX CMT  
SURF Size: 8.625 feet: 260 170 SX CMT

09  
#107

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/10/2004 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/10/2004 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded 5 1/2" casing from 3295' to 2840' w/5 sxs cement.  
Cut casing off at 1460' - pulled one joint casing and spotted 100 sxs cement.  
Pulled casing to 875' - spotted 40 sxs cement.  
Pulled casing to 250' - circulated with 85 sxs cement.  
Pulled all casing - cellar remained full of cement.  
Dakota 158' - 408'. Anhy. 854' - 874'. Salt 1259' - 1425'.  
Total of 225 sxs 60/40 pozmix - 10% gel.

Perfs:

Top	Bot	Thru	Comments
3289	3295		
2892	2896		

RECEIVED  
DEC 16 2004  
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING. EVANS TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

INVOICED

DATE 12-16-04  
INV. NO. 2005060933

DEC 14 2004

JOLLY "J", INC.  
P. O. BOX 872


REPLACEMENT CARD  
#1 "C" KRUG

24-13-14W  
SE SW SW

RUSSELL, KS 67665  
CONTR EMPHASIS OIL OPERATIONS CTY RUSSELL

GEOL \_\_\_\_\_ FIELD KRUG

ELV 1838 KB SPD 12/11/83 CARD ISSUED 5/3/84 # OIL WELL  
1833 GL ARB OH 3289-3295



LOG	Top	Depth	Datum
ANH	.....	854+	984
HEEB	.....	2940-	1102
TOR	.....	2958-	1120
LANS	.....	2998-	1160
BKC	.....	3257-	1419
ARB	.....	3285-	1447
RTD	.....	3295-	1457

API 15-167-22,255

8 5/8 " 260/170SX, 5 1/2 " 3289/150SX  
DST (1) 3255-95 (LKC) / 30-30-0-0, SB, DIED 2", TOOL SLID  
25', RFC 180' M, 10' OCM, ISIP 1063#, IFF 173-183#, HP  
1742-1742#  
MICT - CO, (ARB OH), SWB DWN, SO, POP

INFO RELEASED: 6/14/84 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

INDEXED