

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22491-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 8-6S-21W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: BOYS Well #: 2  
County: GRAHAM Total Vertical Depth: 3715 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W. MAIN - PO BOX 428  
LOGAN, KS 67646

PROD Size: 5.5 feet: 3695 450 SX CMT  
SURF Size: 8.625 feet: 227 160 SX CMT

# 12074

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2004 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JIM R BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 115 sxs Swift Multi-Density cement - 500# hulls - 20 sxs gel spacer.  
Fluid level 2000'.  
5 1/2" with 450 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/09/2004 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 27 sxs Swift Multi-Density cement with 200# hulls,  
followed with 20 sxs gel spacer and 74 sxs SMD with 300# hulls.  
Max. P.S.I. 500#. S.I.P. 200#.  
Hooked up to backside instant 500#.

Perfs:

Top	Bot	Thru	Comments
3434	3625		

RECEIVED  
DEC 16 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

NO.

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 12-16-04

INV. NO. 2005060931

DEC 14 2004

HESS OIL COMPANY  
WICHITA, KS 67202

8-06 -21W  
NW SW NW

#2 BOYS

site: 10-1/2 N & 4 W OF NICODEMUS, KS

city: GRAHAM

API 15-065-22491

contr: MALLARD JV, INC

field: BOYS SOUTH

geol: JAMES C. HESS

fr date 09/30/88      spd date 10/28/88      drlg comp 11/03/88      card issued 03/15/89      last revised 03/15/89


ELV: 2193 KB SMP  
 tops.....depth/datum  
 ANH.....1841 +352  
 B/ANH.....1875 +318  
 TOP.....3202 -1009  
 HEEB.....3406 -1213  
 TOR.....3431 -1238  
 LANS.....3449 -1256  
 BKC.....3636 -1443  
 ARB.....3705 -1512  
 RTD.....3715 -1522  
 NO LOG

**IP status:**  
**OIL, P 18 BO & 110 BWPD, LKC 3434-3625 OA,**  
 CSG: 8-5/8" 227 / 160 SX, 5-1/2" 3695 / 450 SX  
 NO CORES  
 DST (1) 3355-3400 (SHAW), / 30-30-60-45, REC 1650'  
 SW, W / SCUM OIL THRU-OUT ISIP 1000# FSIP 989#  
 IFP 148# -381# FFP 444# -759# IHP 1677# FHP 1666#  
 DST (2) 3395-3470 (SHAW), / 60-30-60-45, REC 10' OIL,  
 60' OCM (20% OIL, 80% M) ISIP 180# FSIP 243# IFP  
 84# -84# FFP 116# -116# IHP 1791# FHP 1677#  
 DST (3) 3580-3640 (LKC), / 30-30-60-45, REC 210' OIL,  
 105' OCM (45% OIL, 55% M) ISIP 169# FSIP 243# IFP  
 127# -137# FFP 158# -169# IHP 2010# FHP 1937#  
 MICT - CO, PF (LKC) 1 / 3625, 1 / 3604 & 3592-3593, W /  
 1 SPF, AC 3000 GAL (15%), SO, PF (LKC) 1 / 3499, 1 /  
 3451 & 3434-3435, W / 1 SPF, AC 3000 GAL (15%), SO,  
 SET 2-3/8" TBG AT 3656, NO PKR, POP, P 18 BO & 110  
 BWPD (GR 37), 11/11/88

COPYRIGHT 1989  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS