

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22425-00-01
Spot: SWSENW Sec/Twnshp/Rge: 8-6S-21W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BOYS B Well #: 1 OWWO
County: GRAHAM Total Vertical Depth: 3740 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W. MAIN - PO BOX 428
LOGAN, KS 67646

PROD Size: 5.5 feet: 3728 475 SX CMT
SURF Size: 8.625 feet: 273 190 SX CMT

121 55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2004 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: JIM R BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered out 115 sxs Swift Multi-Density cement - 500# hulls - 20 sxs gel spacer.
Fluid level 2500'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2004 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 27 sxs Swift Multi-Density cement with 200# hulls,
followed with 20 sxs gel spacer and 89 sxs SMD with 300# hulls.
Max. P.S.I. 800#. S.I.P. 550#.
Hooked up to backside instant 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3388 | 3607 | | |

RECEIVED
DEC 16 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 12-16-04
INV. NO. 2005060931

DEC 14 2004

HESS OIL COMPANY
WICHITA, KS 67202

8-06 -21W
SW SE NW

#1 BOYS "B" QWVVO

site: 10-3/4 N & 3-3/4 W OF NICODEMUS, KS, city: GRAHAM API 15-065-22425-A
contr: MALLARD JV, INC field: BOYS SOUTH
geol: JAMES C. HESS

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

fr date 09/30/88 spd date 10/25/88 drtg comp 10/28/88 card issued 03/15/89 last revised 03/15/89

ELV: 2174 KB LOG
tops.....depth/datum
SC.....1833 +341
TOP.....3188 -1014
OREAD.....3347 -1173
HEEB.....3390 -1216
TOR.....3416 -1242
LANS.....3435 -1261
BKC.....3620 -1446
PENN CONG.....3668 -1494
ARB.....3675 -1501
PBDT.....3709 -1535
RTD OLD.....3740 -1566

IP status:
OIL, P 3 BO & 40 BWP, LKC 3388-3607 OA, PENN
CONG 3670-3780
NOTE: CORRECTION: 9/30/88 - ORIG FR IN NW SE NW;
3/15/89 - ELEV ON REWORK WAS 2179 KB, 2171 GL
OLD INFO: OPERATOR WAS JERRY PATTERSON OIL
COMPANY, 1 BOYS, SPD 11/19/87, 11/25/87 SET 8-
5/8" 273 / 190 SX, D & A, ARB, 11/27/87 (CARD ISSUED
12/23/87)
CONTR: ABERCROMBIE DRILLING, INC
NO CORES
DST (1) 3341-3371 (OREAD), / 30-45-30-60, REC 315'
MCW ISIP 946# FSIP 946# IFP 39# -73# FFP 78#
-137# BHT 108 °

DST (2) 3581-3623 (LKC), / 30-45-5-20, REC 10' SLI OCM ISIP 211# FSIP 388# IFP 52# -52#
FFP 52# -52#
DST (3) 3622-3680 (PENN CONG), / 30-45-30-60, REC 5' OIL, 65' OCM ISIP 1046# FSIP
1003# IFP 73# -73# FFP 73# -73# BHT 108 °
DST (4) 3680-3690 (ARB), / 30-45-30-60, REC 20' SLI OCM ISIP 982# FSIP 898# IFP 42#
-42# FFP 42# -42# BHT 109 °

NEW INFO: FR 09/30/88, RE-ENTERED 10/25/88 WSH DWN TO 3743 DC 10/28/88 CSG: SET
5-1/2" 3728 / 475 SX MICT - CO, PB 3709, PF (PENN CONG) 3670-3680, W / 1 SPF, AC 750 GAL
(15% MCA), SO, PF (LKC) 1 / 3607 & 3575-3576, W / 1 SPF, AC 3000 GAL (15% HCL), SO, PF
(LKC) 1 / 3436, 1 / 3388 & 3417-3418, W / 1 SPF, AC 3000 GAL (15% HCL), SO, SET 2-3/8" TBG
AT 3699, NO PKR, POP, P 3 BO & 40 BWP (GR 27), 12/8/88, COMMINGLED .