

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21917-00-00 <sup>02 KCC afB 12.20.04</sup>  
Spot: SESESE Sec/Twnshp/Rge: 9-14S-13W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: HEINZE Well #: 2  
County: RUSSELL Total Vertical Depth: 2437 feet

Operator License No.: 4952  
Op Name: SCHLOBOHM, STARR F.  
Address: 47 MICHAWANIC ROAD #3D  
SANBORNVILLE, NH 03872

PROD Size: 4.5 feet: 2435 w/100 sxs cmt  
SURF Size: 8.625 feet: 457 w/150 sxs cmt

\$7920

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2004 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2004 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded back casing to 2340' and topped with 5 sxs cement using a dump bailer.  
Cut casing loose at 1800'.  
Pulled casing up to 1500' - mixed and pumped 80 sxs cement with 300# hulls.  
Pulled up to 800' - spotted 40 sxs cement with 100# hulls  
Pulled up to 450' - spotted 30 sxs cement with 100# hulls.  
Pulled up to 200' - circulated cement with 40 sxs cement.  
POOH. Hole full of cement.

RECEIVED  
DEC 17 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

FD.

Signed

Jay Pfeifer  
(TECHNICIAN)

INVOICED


DATE 12-17-04

INVOICE NO. 2005060951

DEC 16 2004

CORIE OIL COMPANY  
 BOX 83  
 RUSSELL, KS 67665  
 CONTR REVLIN DRILLING #2 HEINZE  
 GEOL LEWIS CHUBB CTY RUSSELL  
 ELV 1824 KBSPD 5/10/82 CARD ISSUED 1/13/83 IP TEMP ABD  
 API 15-167-21,917

9-14-13W  
 SE SE SE



DRLRS	Tops	Depth/Datum
ANH	788	+ 1036
GR HAVEN	2345	- 521
SAND	2354	- 530
DOVER	2370	- 546
SAND	2382	- 558
TARK LM	2412	- 588
RTD	2437	- 613

8 5/8 " 457; 4 1/2 " 2435  
 NO DSTS  
 MICT - CO, PF (WAB) INTV NA, ACIDIZED, SWB DWN, SO. POP.  
 NON-COMMERCIAL, TEMP ABD - MAY CONVERT TO TARK WIW -  
 NO OTHER INFO TO BE RELEASED AT PRESENT - WILL RELEASE  
 INFO WHEN AVAILABLE - TEMP COMP - 1/13/83

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

07211100