

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30821-00-02
Spot: NENESE Sec/Twnshp/Rge: 3-19S-15W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEAVER Well #: 2 OWWO
County: BARTON Total Vertical Depth: 2040 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 2028 200 SX CMT
SURF Size: 10.75 feet: 1005

66 30

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/15/2004 11:30 AM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: MIKE KESSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-4879

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Dakota 224' - 499'. Anhy. 976' - 1020'. Salt 1398' - 1698.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2004 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech shot a two hole perf at 450'.
Copeland rigged to 5 1/2" casing - pumped 190 sxs 60/40 pozmix with 400# hulls mixed in.
Circulated cement to surface out of backside.
Shut in backside - pumped 10 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
1888	1894		
1874	1880		

RECEIVED
DEC 17 2004
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #25775.

Plugged through: CSG

District: 04

10

Signed Pat Staab
(TECHNICIAN)

INVOICED

DATE 12-17-04

INV NO 2005060949

Form CP-2/3

DEC 16 2004

LD DRILLING
GREAT BEND KS 67530

3-19S-15W
NE NE SE

#2 WEAVER OWWO


site: 1-1/2 S & 2-1/4 E OF ALBERT KS
contr: LD DRILLING #1

cty: BARTON

API 15-009-30821

field: OTIS-ALBERT

fr date 04/16/2003 spc date 06/05/2003 orig comp 06/05/2003 card issued 02/09/2004 last revised 02/09/2004



ELV: 2004 KB, 1999 GL SMP
tops.....depth/datum
ANH.....976 +1028
B/ANH.....1020 +984
LTD.....1993 +11
HEEB.....3248 -1244
LANS.....3330 -1326
CONG.....3578 -1574
REAGAN SD.....3626 -1622
TD OLD.....3639 -1635
ARF-NOT REACHED
LOGGED

IP status

D&A, REAGAN , 06/12/2003
NOTE: CORRECTION 4/16/2003 - CORR CSG (WAS 979)
OLD INFO: OPERATOR WAS HARBAR DRILLING CO, 1
MERTEN, SPD 03/20/1946, 04/07/1946 10-3/4" 1005 / 425 SX
(ALT 1), D&A, REAGAN , 04/30/1946(CARD ISSUED
04/12/1946)
CONTR: HARBAR DRILLING
COMMENT: WAS TEMP API IOG-8732, NO SIGNFCNT
SHOWS ENCNTRD
DRLR SD ZNS: 240-245

NO CORES OR TSTS

SI - EVAL (4/10/1946), DECISION MADE TO P & A 4/30/1946

NEW INFO: FR 04/16/2003, RE-ENTERED 06/05/2003 WSH DWN TO 2040, LOGGED DC 06/05/2003 CSG:
SET 5-1/2" 2028 / 200 SX

COMMENT: WELL MAY HAVE BEEN RE-ENTERED IN 1952, BUT NO RECORDS AVAILABLE; NO
PLUGGING REPORT; KCC API 15-009-30821-0002; MI & RURT 6/4/2003; GRN LOG RUN 6/10/2003
TRGT ZN: CHASE, REAGAN SD (OIL), PTD 3575 (REAGAN), MICT - CO, FF (CHASE) 1874-1880, 1888-
1894, W / 2 SPF, AC 1250 GAL (15% NEFE), SWB LD, NON-COMMERCIAL, SI - EVAL, DECISION MADE
TO P & A 6/12/2003

ADICEN