

4- 041383

6-23

98P

15-137-00540-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 11-7-79

NESE SE /4 SEC. 25, 05 S, 21 W
990 feet from S section line
330 feet from E section line

Operator license# 5447

Lease Finnigan 'A' well # 2

Operator: OXY USA, Inc.

County Norton

Address: 110 S. Main
#800
Wichita, Kansas 67202

Well total depth 3675 feet ^{119.43}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 206 feet
w/250 sx.cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Titan License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 23 Month: June Year: 92

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 5 1/2" casing set @ 3672'. T.D. 3675'. O.H. 3672' - 3675'. Perf.
Dakota @ 1125'. Perf @ 1825'. T.O.F. 2200'.
Ordered 400 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:40P.M., Day: 23, Month: June, Year: 92

Actual plugging report: Hooked-up to 5 1/2" casing. Squeezed in 300
sx. cement w/400# hulls in cement. Max. 800#. S.I.P. 150#.
Hooked-up to 8 5/8" S.P. Pumped in 100 sx. cement w/100# hulls.
Max. 600#. S.I.P. 400#.

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1992
CONSERVATION DIVISION
Wichita, Kansas

7-6-92

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] did not [] observe the plugging.

Dennis L. Hamel

HO

(agent)

Form CP-2/3

INVOICED

DATE 7-7-92

INV. NO. 35631