

4-041379 6-23

15-137-00028-00-00

100  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 2-28-46

SWSE SE /4 SEC. 25, 05 S, 21 W  
330 feet from S section line  
990 feet from E section line

Operator license# 5447

Lease Finnigan 'A' well # 1

Operator: OXY USA, Inc.

County Norton

Address: 110 S. Main  
#800  
Wichita, Kansas 67202

Well total depth 3683 feet <sup>119.69</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 157 feet  
w/125 sx.cmt.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B.J. Titan License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 23 Month: June Year: 92

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 5 1/2" casing set @ 3678'. T.D. 3683'. O.H. 3678' - 3683'.  
Dakota @ 1125'. W.L.M. ran tubing. Casing squeezed @ 3030' - 2862' -  
2709' - 2570' - 1848' - 185' - 160' with a total of 400 sx. cement.  
Ordered 400 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:30A.M., Day: 23, Month: June, Year: 92

Actual plugging report: Ran in hole with tubing to 2022'. Spot 115 sx.  
cement with 200# hulls in cement. Cement circ. to surface.

P.O.O.H. with tubing. Hooked-up to 5 1/2" casing squeezed 160 sx. cement  
with 200# hulls mixed in cement. Max. 1000#. S.I. 650#.

Hooked up to 8 5/8" annulus, pressured up to 450#.

JUL 6 1992

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING X, CASING    . Elevation:     GL

I did X / did not [     ] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 7-7-92

INV. NO. 357633