

5-18-87 13-137-20097-00-00

6 030882

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION CS/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 4-16-75

SE SE, SEC. 23, T 5 S, R 21 W/E

330 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Kemper Well # 1

Operator: Baird Oil Co. Inc.

County Norton 117.72

Name & Address Box 428

Well Total Depth 3622 feet

Logan, Kansas 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 214'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 18 Month: May Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 8 5/8" set at 214' cwc 4 1/2 set at 3615' with 235 sx G1 2189' open hole. T.O.C. 2400' order com. snad and cmt. Shoot and strip pipe - order

150 sk ATL 65/35 poz 10% gel 2% dicel 5 sx hulls Allied Cmt. Co.

Plugging Proposal Received by Dale Balthazor and Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 PM Day: 18 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT And bottom to 3550 with 4 sx com. cmt. on sand with bailer.

With stretch on pipe one shot at 2554' parted pipe at 242' recovered 242' of csg. mix and pump sown 8 5/8" csg. 5 sx hulls with 150 sk ATL cmt. blend. Max PSI 600 # close in 150# PSI plug complete.

Remarks: Plugs checked by Dale B. OK (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COM 7-28-87 JUL 28 1987

INVOICED (If you do not observe this plugging.

TE 7-29-87 NO. 17638

Signed Carl Goodrow (TECHNICIAN) DB