

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23074-00-00  
Spot: SESESE Sec/Twnshp/Rge: 36-22S-12W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: RICHARDSON Well #: 1-A  
County: STAFFORD Total Vertical Depth: 3324 feet

Operator License No.: 32432  
Op Name: LA VETA OIL & GAS, LLC  
Address: PO BOX 780  
MIDDLEBURG, VA 20118

PROD Size: 5.5 feet: 3324 WITH 125 SX CMT  
SURF Size: 8.625 feet: 337

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2004 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 2691' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 10/15/2004 3:45 PM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 2691' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2772	2781		

RECEIVED  
DEC 16 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND. RECOVERED 2020' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED  
DATE 12-16-04  
INV. NO. 2005060940

Form GR-33  
*[Signature]*