

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-00088-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 19-18S-31W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: CHANCE Well #: 1
County: SCOTT Total Vertical Depth: 4012 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: P.O. BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 3998 WITH 700 SX CMT
SURF Size: 8.625 feet: 287 WITH 250 SX CMT

39
130

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2004 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: WAYNE GERSTNER Company: BEREN CORPORATION Phone: (316) 772-1155

Proposed Plugging Method: SAND TO 3900' WITH 5 SX CMT. TEST CASING TO 300#. PERFORATE AT 1600'. GET RATE. PUMP 80 SX CMT. RUN TUBING TO 800'. PUMP 20 SX CMT. CMT FROM 287' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2004 2:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SAND TO 3900' WITH 5 SX CMT ON TOP. LOAD CASING WITH FRESH WATER. TEST CASING TO 500#. HELD. PERFORATE CASING AT 1600'. PUMP 2 BBL CMT. BLEW SHALLOW HOLE IN 5 1/2" AT 1000#. CIRCULATE CMT OUT OF CASING. RAN CMT RETAINER ON WIRE LINE TO 1500'. PUMP 50 SX CMT INTO PERFS. SQUEEZED TO 800#. PULL TO 800' & PUMP 20 SX CMT. PULL TO 300' & PUMP 30 SX CMT TO SURFACE. CMT CIRCULATED. PUT SWEDGE IN 5 1/2" CASING WITH VALVE. PUMP 10 SX CMT DOWN BACKSIDE. SHUT IN PRESSURE 500#.

Perfs:


Top	Bot	Thru	Comments
3998	4012		
3958	3960		

RECEIVED
DEC 16 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 3% CC BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed _____

(TECHNICIAN)

INVOICED
DATE 12-16-04
WEL. NO. 2005060934

FORM CR-2/3